


Base Weight = 6500 lbs.
 Wall Weight = 3500 lbs.
 Total Weight = 10,000 lbs.



Reinforcing Schedule

Walls: 1 layer #4 rebar matt centered in wall
 1/2" rebar 48" long wrapped around cnrs @ 18" o.c.
 Base: 1 layer 5/8 rebar @ 12" o.c.

DARNALL CONCRETE PRODUCTS COMPANY
7/29/11
9' x 8' x 24" Fuel Storage Vault