


Base Weight = 10000 lbs.
 Wall Weight = 5600 lbs.
 Total Weight = 15,600 lbs.



Reinforcing Schedule

Walls: 1 layer #4 rebar matt centered in wall
 1/2" rebar 48" long wrapped around cnrs @ 18" o.c.
 Base: 1 layer 5/8 rebar @ 12" o.c.

DARNALL CONCRETE PRODUCTS COMPANY
7/29/11
9'0"x 13' x 30" Fuel Storage Vault